


Bram Herfkens, project manager Storage 5th International workshop on offshore CCS, 19 May 2022






Technical Aspects of Depleted Gas Fields







Gasfield Containment & Seismicity


Thermodynamics

Permits & Lookahead




Porthos






Re-use of depleted gas fields



Re-use of Platform



New compressor station

Reuse of Facilities

- Life time extension assessment
- Maintenance philosophy: from break-down to preventive
- Concurrent operations: gas production & CO2 injection
- Change operations & logistics to daylight only and boat access
- Gas price development impacts cease of production dates



Re-use of gas wells

Well integrity


- Cement bond logs reliable?
- Status of casing, liners and conductors
- Annulus pressures

Well Design

- New completions
- Thermal loads and tubing of Cr25
- DTS / DAS monitoring
- Developed SSSV's for arctic conditions

Well Containment

- Thermal loading: debonding of casing-cement-rock face
- Hydrostatic head/pressure as containment barrier




Closure of gas production wells



Well Abandonment:

- Re-entry of suspended wells
- Complex wells, not designed for re-use or re-entry
- Full bore formation plugs become the standard?

Successful well campaign pre-FID to de-risk the project







Risk Management Storage

1 Containment Risk

2 Seismic Risk

3 Operational Risk

4 Commercial Risk

- Migration
- Leakage

PERMIT REQUIRED

- Earthquake
- Leakage

PERMIT REQUIRED

Flow Assurance and control

- Injectivity
- Storage Capacity


Key Technical Aspects


A.Containment

- 1. from the reservoir laterally
- 2. from the reservoir vertically
- 3. from injection wells, during injection
- 4. from wells after plugging and abandoning

B.Seismicity

5. Fault slippage -> "earthquake"






Storage in depleted fields is new




- Gas fields have a proven geological containment
- Reservoir pressure is low (20 bar, was >350 bar)
- CO2 transport is high pressure, dense mode
- Challenge is pressure drop
- Temperature drops with pressure drop
- Low temperatures in wells and reservoir
- Reservoir pressure will remail lower than (CO2) virgin pressure
- CO2 specification affects phase behaviour



Reservoir modeling








Reservoir modeling

Thermal effects and seismicity







- Porthos received the concept storage permits from the regulator (MEA).
- Now awaiting European committee advise and definitive permits
- Porthos permit was first of its kind.
 - How will other projects approach this?
 - How will authorities deal with defferences?






Look ahead



Current

- Permit procedures
- Decommissioning of well
- FID deliverables
- European tenders construction compressor station and offshore pipeline
- Second half of 2022
 - Final Investment Decision (FID)
- 2023
 - Start construction
- 2024/2025
 - System operational





The contents of this presentation are the sole responsibility of Porthos and do not necessarily reflect the opinion of the European Union.



