Session 2 International Project Roundup INEOS Energy efforts to Develop the CCS Value Chain in Denmark



CO2 Exploration in Denmark – Gassum (Greenstore) secured with start-up expected 2029

Greenport Scandinavia



INEOS Energy Offshore Pipeline transport and Storage Ship transport & Storage In situ Capture & Storage Onshore pipeline & Storage CC Hubs for U and/or S. Northern light Greenport Scandinavia Greensar Coast/Endurance Interconnector Ravenna Disclaimer: Map produced by Greensand Project based on available public data, not complete and only illustrative

Greensand Project


Safe and Reliable Offshore Transport and Storage of CO₂ in the Danish Sector of the North Sea

A project underway by INEOS Energy, Harbour Energy and Nordsøfonden


Greensand Project – Offshore Transport and Storage of CO2 Overview



- Use of Siri Area for CO₂ storage
 INEOS has experience and huge data set from exploration and production activities in Siri Area over more than 20 years
- Offshore Pilot CO2 Injection and Monitoring test in 2023
- Initial Greensand work focused on CO₂ storage in Nini West Proof of commercial Scale
- Greater Greensand Expansion Area includes remaining Siri area suitable reservoirs – harvest economies of scale




Greensand Greater Expansion Area





Pilot Injection


CO₂ injection successfully performed in early 2023



Demonstration of full value chain from capture to storage + test of monitoring techniques




Meeting the Emitters by Scaling Up CO₂ Storage Capacity




Confide

Hydonal Occanography Centra EUDP C

Greensand – Commercial Project #1





Opportunity:

- Storage of available biogenic CO₂ from biogas.
- Negative emissions Carbon credits sale
- Modified bulk carrier design ~5.000 tCO₂/trip
- Build on Phase 2 pilot learnings hardware and operation
- 300-400 kTon CO2 per year (pending logistical set-up)

Key Milestones:

- Submission of storage site application February 2024.
- Funding application submitted to EUIF
- End 2024: Project sanction.
- End 2025/Start 2026: First CO₂ injection.

